(Material supplied by Dariush Borbor)

The erection sequence was, first, to fix the precast spiral treads; second, to weld the steel uprights to steel angles cast into the treads taking one rise at a time; third, to lower each curved precast baluster slab on to steel angles welded to the flanges of the uprights and grout in. A further length of steel upright was then bolted on and the cycle repeated. English readers will envy the quality and precision of the curved panels.



